D. WAINMAN

Swinden Laboratories

Report No.	RS/R/S1199/ 86/B
Date	23 SEPTEMBER 1986
Classification	CONFIDENTIAL - RESTRICTED

The Fire Resistance of Four Shelf Angle Floor Constructions - BS476: Part 8 Fire Tests Carried out Between 24th May 1984 and 19th December 1984

The circulation of this report is restricted to staff of the British Steel Corporation and externally to those named in the circulation list

British Steel Corporation

Research Organisation



THE FIRE RESISTANCE OF FOUR SHELF ANGLE FLOOR CONSTRUCTIONS
- BS476:PART 8 FIRE TESTS CARRIED OUT BETWEEN
24TH MAY 1984 AND 19TH DECEMBER 1984

G. Thomson

D.J. Latham

R.R. Preston

SYNOPSIS

The report summarises the results from BS476:Part 8 fire tests carried out on four separate shelf angle floor constructions based on the use of an unprotected $406 \times 178 \text{ mm} \times 54 \text{ kg/m}$ universal beam. A BS4360:Grade 43A beam was incorporated in three assemblies and a Grade 50B beam in the fourth. Precast concrete floor slabs, either 200 mm or 100 mm thick and 550 mm wide were supported on 125 x 75 x 12 mm angles bolted to the web of the beam. The steel beams were subjected to different applied loads, as based on BS449.

The fire resistance of each assembly was influenced by the extent of the partial protection afforded by the floor slabs and the load applied to the beam. Both the Grade 50B beam loaded to 43% of the maximum design value and the Grade 43A beam at 80% of the maximum load exceeded the 1 h fire rating with 200 mm thick concrete slabs. Neither of the Grade 43A beams with 100 mm thick slabs loaded respectively to 100% and 60% of the maximum design value were as satisfactory, but in the latter design a fire resistance of 74 min was obtained by prolonging the test to a deflection of L/20.

KEY WORDS

- 3. Fire Resistance
- 4. Floorings
- Deflection
- Testing

- 7. Shelf Angles
- 8. +BS 476
- 9. Lab Reports
- 10. Concrete

RS/R/S1199/2/86/B

CONTENTS			PAGE
1.	INTRODUCTION		1
2.	DETAILS OF CONSTRUCTION		1
3.	TEST RESULTS		2
4.	DISCUSSION		5
5.	CONCLUSIONS		5
6.	REFERENCES		6
	3 DDEND TOTO		

THE FIRE RESISTANCE OF FOUR SHELF ANGLE FLOOR CONSTRUCTIONS - BS476:PART 8 FIRE TESTS CARRIED OUT BETWEEN 24TH MAY 1984 AND 19TH DECEMBER 1984

INTRODUCTION

When a fire breaks out in an enclosure the temperature of any steel section within it will rise at a rate depending upon its Hp/A ratio. If the steel section is not fully exposed to the fire its Hp/A is effectively reduced resulting in a lower heating rate and an increase in the fire resistance time.

The concept of partial protection can be extended to shelf angle floor systems which are used in the design of multi-storey buildings to reduce the floor/ceiling void depth. Two BS476:Part 8 fire tests were carried out on unprotected BS4360:Grade 43A beams of serial size 406 x 178 mm x 54 kg/m and 305 x 165 mm x 40 kg/m respectively which were used as part of a fully loaded shelf angle floor construction^{1/2}. These results suggested that the use of such a design might satisfy the requirements of the Building Regulations for '1 h' buildings. However, further testing was required to determine the behaviour of other similar floors and to provide suitable 'bench mark' observations for the derivation of a mathematical model able to predict the fire resistance of the appropriate range of beam sizes, floor depths and applied loadings used in this form of design.

The present report summarises the results from four BS476:Part 8 fire tests on shelf angle floor constructions, comprising 406 x 178 mm x 54 kg/m BS4360 Grade 43A beams, 125 x 75 x 12 mm BS4360 Grade 50B angles and 200 mm or 100 mm thick precast concrete floor slabs. The steel beams were subjected to different applied loads, based on BS449 and fire tested at the Warrington Research Centre between 24th May 1984 and 19th December 1984.

2. DETAILS OF CONSTRUCTION

2.1 Steel Supply

The steel sections used in each construction were obtained either from a local steel stockholder or from Lackenby Works and comprised:-

```
5 m 406 x 178 mm x 54 kg/m universal beam (BS4360)
2 x 5 m 125 x 75 x 12 mm angles (BS4360:Grade 50B)
```

Samples were taken from each of the sections for chemical analysis and mechanical testing. The compositions are given in Table 1 and the mechanical properties in Table 2. One beam was found to comply with BS4360 Grade 50B, the remaining beams were within the limits specified for BS4360 Grade 43A and the angles were within the compositional tolerances of BS4360:Grade 50B.

2.2 Fabrication of Sections

The angles were positioned on either side of the beam to leave a 210 or 110 mm gap between the upper flange of the beam and the 125 mm leg of the angle. The shorter leg of the angle was located within the gap. Holes were drilled at 600 mm centres along the mid axis of the 75 mm angle leg to accommodate M20 8.8 grade bolts. In the earlier test M20 4.6 grade bolts had been used, two of which failed at one end of the test arrangement located outside the furnace. A schematic illustration showing the test assembly is given in Fig. 1.

2.3 Concrete Slabs

The concrete slabs were similar to those used in earlier tests and were cast into $1550 \times 550 \times 200$ mm thick blocks, or $1550 \times 550 \times 150$ mm thick blocks with one end tapering to 100 mm thick over a distance of 300 mm. The concrete contained steel reinforcement as shown in Fig. 2 and complied with BS8110:Grade 30 compressive strength.

2.4 Instrumentation

A total of 32 mineral insulated thermocouples of the chromel/alumel type, each with insulated hot junctions and an Inconel sheath were used to monitor the heating rate of the steel during each test. The thermocouples were located at the positions shown in Fig. 3; in summary, five thermocouples were embedded in the lower flange of the beam, four thermocouples in the exposed part of the web, four were attached to the protected part of the web and four were attached to the upper flange of the beam. These thermocouples were located around the central part of the beam.

Nine thermocouples were embedded in the shelf angles, three on the exposed leg, three on the unexposed leg and three on the root of the angle.

Thermocouples were also installed after the construction was assembled to monitor furnace atmosphere temperatures at six positions along the beam adjacent to the lower flange.

2.5 Assembly

The beam with the angles attached was placed on the furnace in the standard position to give an effective length of 4.5 m between the roller supports. Each slab was then manoevred into position between the shelf angle and the upper flange to utilise a 75 mm load bearing length on the shelf angle. This left a gap of 50 mm between the end of the slab and the web of the beam. The other end of the slab rested on a wall which was built along the edges of the furnace level with the shelf angle. A 12 mm gap was left between the slab and wall at the ends of the beam, thus enabling the slabs to move freely with the beam as it deflected vertically. Ceramic fibre blanket material was used to cover the gaps at both ends.

Once the 16 slabs were in position the 50 mm gap between the slab end and web was completely filled in with dried sand. The upper flange of the beam was also covered with a 25 mm layer of sand in order to simulate the thermal characteristics of a floor screed which is used in site practice.

Photographs of the construction during assembly are shown in Figs. 4 and 5.

2.6 Loading

The load to the beam was applied through the concrete slabs and angles to simulate service conditions. Four hydraulic jacks were positioned on either side of the beam at a distance of 0.5 m from its centreline. Loads were applied to eight points onto the concrete slabs using 1 m lengths of 152 x 152 mm x 23 kg/m universal column as load spreaders. Details of the loading calculations used in each test are given in Appendix 1. A photograph of the completed construction is shown in Fig. 6.

Deflection measurements were taken at the centre of the beam by the Warrington Research Centre staff using their potentiometric system. Additional measurements were also taken from the central concrete slab using a theodilite system.

TEST RESULTS

It is convenient to consider the four tests separately and in the following order.

3.1 Grade 50B Beam - Test A

Loaded to a design stress of 100 N/mm^2 using 200 mm thick concrete floor slabs. This construction achieved a fire resistance period of 94 min, at which time the L/30 failure criterion in the BS476:Part 8 fire test was reached.

3.1.1 Deflection Measurements

The deflection measurements made on the beam at the centre of the construction in Test A are shown in Fig. 7. The rate of deflection was greater in the first 30 min of the test but thereafter remained almost constant until failure occurred.

3.1.2 Temperature Measurements

A summary of steel temperatures and furnace atmosphere temperatures at various stages during the test is presented in Table 3.

The furnace atmosphere heating curves are compared with the International temperature/time curve in Fig. 8 which shows that the heating rate was generally in accordance with the standard curve throughout the test.

Average heating curves recorded at different positions across the shelf angle beam are compared in Fig. 9. At failure there was little scatter between the temperatures measured on the lower flange which were within the range 985 to 999°C with a mean of 992°C. The final temperatures in the exposed web were within the range 964 to 981°C with a mean of 974°C; the corresponding temperature range in the unexposed part of the web was between 229 and 257°C with a mean of 243°C. The upper flange reached a mean temperature of 103°C. The final average temperatures of the exposed and unexposed angle flanges were 945 and 716°C respectively.

3.1.3 Observations

In order to check an equipment malfunction it became necessary to remove the load after 16 min into the test which was then reapplied within 60 s. The concrete slabs developed a stepwise pattern as the beam deflected and several units exhibited vertical and shear edge cracks at the end of the test. The angles deformed in a uniform manner.

All the bolts remained intact after the reload test.

3.2 Grade 43A Beam - Test B

Loaded to a design stress of 132 N/mm^2 using 200 mm thick concrete slabs. This construction achieved a fire resistance time of 70 min at a deflection of L/30.

3.2.1 Deflection Measurements

The deflection measurements made on the beam at the centre of the construction in Test B are shown in Fig. 10.

3.2.2 Temperature Measurements

A summary of steel temperatures and furnace atmosphere temperatures at various stages during the test is presented in Table 4.

The furnace atmosphere heating curves are compared with the International temperature/time curve in Fig. 11, which shows that the heating rate was generally in accordance with the standard curve throughout the test.

Average heating curves recorded at different positions across the shelf angle beam are compared in Fig. 12. At failure there was little scatter between the temperatures measured on the lower flange which were within the range 910 to 922°C with a mean of 914°C. The final temperatures in the exposed web were within the range 878 to 898°C with a mean of 890°C; the corresponding temperature range in the unexposed part of the web was between 173 and 219°C with a mean of 191°C. The upper flange reached a mean temperature of 94°C. The final average temperatures of the exposed and unexposed angle flanges were 839 and 613°C respectively.

3.2.3 Observations

The shelf angle floor assembly satisfied the reload test. Nothing unusual occurred during the test.

3.3 Grade 43A Beam - Test C

Loaded to a design stress of 100 N/mm 2 using 100 mm thick concrete slabs. This construction achieved a fire resistance time of 43 min at a deflection of L/30 and 74 min at a deflection of L/20.

3.3.1 Deflection Measurements

The deflection measurements made on the beam at the centre of the construction in Test C are shown in Fig. 13. The rate of deflection increased to a maximum of 4 mm/min and decreased to 2 mm/min after 45 min.

3.3.2 Temperature Measurements

A summary of steel temperatures and furnace atmosphere temperatures at various stages during the test is presented in Table 5.

The furnace atmosphere heating curves are compared with the International temperature/time curve in Fig. 14, which shows that the heating rate was generally in accordance with the standard curve throughout the test.

Average heating curves recorded at different positions across the shelf angle beam are compared in Fig. 15. At failure there was little scatter between the temperatures measured on the lower flange, which were within the range 907 to 921°C with a mean of 915°C. The final temperatures in the exposed web were within the range 889 to 909°C with a mean of 900°C; the corresponding temperature range in the unexposed part of the web was between 287 and 340°C with a mean of 317°C. The upper flange reached a mean temperature of 222°C. The final average temperatures of the exposed and unexposed angle flanges were 804 and 616°C respectively.

3.3.3 Observations

The 100 mm thick concrete slabs were used for the first time in a BS476:Part 8 fire test on a shelf angle assembly and behaved in a similar manner to the thicker blocks. After the test, some of the slabs exhibited cracking (Fig. 16(a)). The deflection of both the beam and angle was uniform (Fig. 16(b)). The assembly satisfied the reload test and all the bolts remained intact.

3.4 Grade 43A Beam - Test D

Loaded to a design stress of 165 N/mm^2 using 100 mm thick concrete slabs. This construction achieved a fire resistance time of 29 min at a deflection of L/30. Copies of the letters received from the WRC confirming the general results from each test are given in Appendix 2.

3.4.1 Deflection Measurements

The deflection measurements made on the beam at the centre of the construction in Test D are shown in Fig. 17.

3.4.2 Temperature Measurements

A summary of steel temperatures and furnace atmosphere temperatures at various stages during the test is presented in Table 6.

The furnace atmosphere heating curves are compared with the International temperature/time curve in Fig. 18 which shows that the heating rate was generally in accordance with the standard curve throughout the test.

Average heating curves recorded at different positions across the shelf angle beam are compared in Fig. 19. At failure there was little scatter between the temperatures measured on the lower flange, which were within the range 724 to 738°C with a mean of 733°C. The final temperatures in the exposed web were within the range 707 to 724°C with a mean of 715°C; the corresponding temperature range in the unexposed part of the web was between 152 and 180°C with a mean temperature of 167°C. The upper flange reached a mean temperature of 97°C. The final average temperatures of the exposed and unexposed angle flanges were 571 and 368°C respectively.

3.4.3 Observations

Six minutes after the start of the test white fumes were emitted from the concrete slabs and these were present throughout the test. On completion of the experiment

the majority of the slabs contained either shear or vertical edge cracks which were located in the tapered portion of the slab and originated from the vicinity of the flange tip.

4. DISCUSSION

The serial size of beam used in these experiments has never been subjected to a BS476:Part 8 fire test in the unprotected form. However, a study of the changing temperature distributions measured across other unprotected steel members tested in this way suggests that a fire resistance for the 406 x 178 mm x 54 kg/m beam of 19 min would be expected when loaded to maximum design load (BS449). If the temperature profiles are used as input data to the FASBUS II finite element programme which calculates the changes in stress and deflection a fire resistance of 23 min is predicted for a BS4360:Grade 43A section and 21 min for a Grade 50B section.

However, during a fire beneath a shelf angle floor beam the concrete floor keeps the temperatures of the top flange and the upper parts of the web to modest levels. The net result is that as the bottom flange gets hotter and gradually loses some of its load bearing capacity the neutral axis shifts upwards and tensile loads begin to be taken up by the shelf angles. Hence, the time to failure under load is longer than for bare unprotected beams having the floor slabs resting on the top flanges. Clearly, the use of different precast concrete floor slab thicknesses provide more or less protection to the web of the beam. In an earlier test in which the BS4360:Grade 43A beam in a shelf angle floor construction incorporating 200 mm thick concrete slabs was loaded to the maximum design value a fire resistance time of $67\frac{1}{2}$ min was observed. The use of 100 mm thick slabs in the present exercise reduced the fire resistance time to 29 min.

Previous work on unprotected steel beams showed that the fire resistance was improved by reducing the stress in the centre of the tensile flange of the beam. A similar effect occurred in the shelf angle floor tests. For example, with a floor thickness of 100 mm the fire resistance time increased by 14 min as a consequence of reducing the applied load by 40%.

The shelf angle floor design offers the scope for achieving a 1 h fire resistance without recourse to passive protection. If the benefits offered by this form of construction are to be recognised in the high percentage of building designs requiring such fire resistance it is necessary to evaluate the behaviour of all potential systems. The current study has provided valuable benchmark data for use in the development of a mathematical model for predicting the performance of the remaining sections without incurring the expense of fire testing.

5. CONCLUSIONS

Four BS476:Part 8 fire tests were carried out on shelf angle floor constructions based on a 406 x 178 mm x 54 kg/m universal beam and 125 x 75 x 12 mm angles supporting either 200 mm or 100 mm thick precast concrete slabs. The assemblies were subjected to different applied loads, based on BS449.

The BS4360 Grade 50B beam loaded to a design stress of 100 N/mm^2 using 200 mm thick slabs achieved a fire resistance of 94 min.

The BS4360 Grade 43A beam loaded to a design stress of 132 $\rm N/mm^2$ using 200 mm thick slabs achieved a fire resistance of 70 min.

The BS4360 Grade 43A beam loaded to a design stress of 100 N/mm^2 using 100 mm thick slabs achieved a fire resistance of 43 min and 74 min at a deflection of L/20.

The BS4360 Grade 43A beam loaded to a design stress of 165 N/mm^2 using 100 mm thick slabs achieved a fire resistance of 29 min.

6. REFERENCES

- Thomson, G., Hogan, G. and Smith, C.I., Sheffield Laboratories Report No. SH/RS/3664/1/83/B.
- Thomson, G., Hogan, G. and Latham, D.J., Swinden Laboratories Report No. SH/RS/3664/5/84/B.

G. Thomson Investigator

D.J. Latham Principal Investigator

R.R. Preston Manager, Rails and Sections Department

J. Lessells Research Manager -General Steel Products

CHEMICAL COMPOSITION OF THE STEEL SECTIONS USED IN THE FIRE TESTS

TABLE 1

	υ	Si	R	Δ	s	Ç	Mo	Ni	Al	Cu	N	Nb	Sn	Λ
RS550 406 x 178 mm x 54 kg/m UB RS551 125 x 75 x 12 mm Angle Tested 24.5.84	0.18 0.015	0.015	1.39 0.026	0.018	0.015	0.03	0.005	0.03	0.004	0.03	0.003	0.001	0.003	0.088
RS558 406 x 178 mm x 54 kg/m UB 0.20 0.027 RS559 125 x 75 x 12 mm Angle 0.14 0.22 Tested 26.6.84	0.20		0.92	0.014	0.028	0.02	0.004	0.01	0.006	0.02	0.005	0.001	0.003	0.001
RS560 406 x 178 mm x 54 kg/m UB RS561 125 x 75 x 12 mm Angle Tested 11.7.84	0.22 0.03		0.89	0.026	0.025	0.04	0.004	0.03	0.004	0.04	0.005	0.001	0.005	0.001
RS640 406 x 178 mm x 54 kg/m UB 0.21 0.038 RS641 125 x 75 x 12 mm Angle 0.16 0.21 Tested 19.12.84	0.21		0.96	0.024	0.012	0.02	0.005	0.02	0.008	0.02	0.004	0.001	0.005	0.002
BS4360 Grade 43A Product Analysis	0.30 max.	0.55 max.	1.70 max.	0.06 max.	0.06 max.				/					
BS4360 Grade 50B Product Analysis	0.24 0.55 max. max.	0.55 max.	1.60 0.06 max. max.	0.06 max.	0.06 max.							0.003/	•	0.003/

TENSILE TEST RESULTS FROM THE BEAMS AND ANGLES USED IN THE FIRE TESTS

TABLE 2

Elongation	29 30	36 32	32 32	30	20 min.	18 min.
Tensile Strength N/mm ²	564 575	467 539	478 518	499 562	430/540	490/620
Yield Stress N/mm ²	407 397	300 380	280 381	335 404	255 (min.)	355 (min.)
Identity	RS550 406 x 178 mm x 54 kg/m UB RS551 125 x 75 x 12 mm Angle Tested 24.5.84	RS558 406 x 178 mm x 54 kg/m UB RS551 125 x 75 x 12 mm Angle Tested 26.6.84	RS560 406 x 178 mm x 54 kg/m UB RS561 125 x 75 x 12 mm Angle Tested 11.7.84	RS640 406 x 178 mm x 54 kg/m UB RS641 125 x 75 x 12 mm Angle Tested 19.12.84	BS4360 Grade 43A Specification	BS4360 Grade 50B Specification

ANGLE FLOOR TEST 06 x 178 x 54 kg, 25 x 75 x 12 mm	4 1	TEMPERA Grade 50 Grade 50	티 " #	RE DAT	8 0	EET este	a A	438 0	f desi	ign lo	a g	BS449)					Date		24.5	. 84
																	Failur	e Time	94 m	min
						T.	empera	ture	°C,	After	Vario	ous Tim	es,	min						
3 6 9 12	12	10	15	18	21	24	27	30	35	40	45	50 5	5 6	9 0	5 70	75	80	8.5	9.0	94
61 153 270 391	-	-	488	3 558	612	099	969	723	750	783 8	15 8	43 8	88 89	88 90	7 92	5 942	957	971	984	994
57 146 267 389 65 166 298 412 58 150 270 393 95 187 312 425	389 412 393 425		487 500 490 507	7 558 0 567 0 560 7 568	614 615 611 619	662 660 659 661	700 696 696 694	726 722 721 720	752 749 747 746	786 8 781 8 780 8 779 8	117 8 113 8 111 8 107 8	34 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8	71 89 66 86 63 88 58 87	92 91 89 90 83 90 78 89	12 929 06 924 02 921 99 911	9 946 1 940 1 937	962 956 953 948	975 970 967 963	984 982 960 970	999 992 989 985
67 160 283 402		2	494	4 562	614	099	969	722	748	781 8	812 8	40 8	65 92	22 90	5 92	2 939	955	696	976	992
76 167 261 360 4 75 159 266 372 4 81 170 283 383 4 90 180 279 375 4	1 360 6 372 3 383 9 375		4.0.00	2 5 0 2 3 5 0 9 5 0 9	557 571 578 578 563	606 620 625 609	642 656 662 645	672 686 692 673	712 723 729 711	740 7 749 7 754 7 739 7	68 7 80 8 86 8	99 8 12 8 16 8 96 8	27 86 40 86 44 86 24 85	54 87 65 88 67 88 50 87	75 894 16 905 18 907 70 890	913 923 7 926 0 908	930 941 942 924	946 956 956 941	960 970 971 955	971 980 981 964
80 169 272 372	~	2	15.	3 512	567	615	651	680	718	745 7	74 8	05 8	34 85	59 87	6 8 8	9 917	934	949	964	974
20 21 26 30 20 21 26 31 19 21 27 32 19 21 26 31	31 31 31		37 37 37 37	6 4 4 5 7 4 5 5 4 5 5 4 5 5 4 5 5 4 5 5 4 5 5 6 5 6	0.	58 63 62	68 75 75 71	78 88 88 84	97 110 106	108 127 118 121 121	20 1 28 1 34 1	31 1 53 1 39 1	42 /15 65 17 50 16 43 14	53 16 77 19 63 17 48 15	173 173 10 202 16 188 162	2 143 2 214 3 199 2 176	195 226 210 193	207 236 223 210	220 249 232 228	229 257 246 240
19 21 26 31	6 31		m	7 45	53	61	72	84	104	118 1	31 1	41 1	50 16	60 17	70 181	193	206	219	232	243
18 19 22 23 2 19 20 22 22 2 20 20 23 22 2	23 22 22		(0 24 0 24 0 24	21 21 21 21	23 22 22	26 27 27	29 28 28	34 32	141 36	45 37	53	55	87 8 77 7 73 7	0.88	3 98 2 91 9 103	101	101	103	103 102 105
19 19 22 22 2	2 22			0 24	21	22	27	29	34	39	41	53 (79 8	2	8 97	102	102	103	103
43 86 156 217 27 47 85 146 207 26 50 87 140 199 25	217 2 207 2 199 2	222		1 329 3 322 7 316	381 382 373	442 442 433	488 496 485	526 541 528	581 601 593	631 6 651 6 640 6	76 7 96 7 84 7	14 7 34 7 21 7	53 7	72 80 94 82 78 81	0 8 3 2	3 859 4 882 9 867	884 908 891	905 927 910	925 946 927	938 959 939
46 86 147 207 26	7 207 2	7		3 322	378	439	489	531	591	640 6	85 7	23 7	26 78	81 81	3 84	2 869	894	914	932	945
22 41 83 92 12 22 38 60 91 12 23 39 62 93 12	92 1 91 1 93 1		: - : -	7 165 5 165 9 171	204	242 245 252	278 284 291	312 321 326	363 372 374	407 413 415	447 448 455 4	82 84 93 5	16 19 56 56	48 57 50 58 61 59	9 0 6 0 6 1	5 629 5 630 7 643	652 654 667	672 676 689	693 698 711	708 714 726
22 39 68 92 13	8 92 1	1	7	7 167	206	246	284	319	369	411 4	450 4	86 5	21 5	53 58	3 60	9 634	657	629	700	716
27 53 91 133 1 27 50 83 121 1 27 49 87 113 1	133 1 121 1 113 1		56.7	8 225 5 211 6 202	271 258 2248	318 308 296	363 356 343	404 400 386	464 464 451	515 518 502	561 566 549	602 606 606 6606 67	24 24 21 21 6	71 69 74 70 53 68	8 72 2 72 0 70	4 749 8 753 4 728	775	799 804 776	824 828 798	841 844 816
27 50 87 122	7 122		16(6 212	2 259	307	354	396	459	511	558	9 869	33 60	69 99	93 730	743	1 768	793	816	833
502 603 663 705 7 5 12 26 36	687 705 36		- E 4	4 73 8 76 6 5	4 776 6 789 5 63	792 808 69	800 826 77	827 842 80	846 865 88	863 885 96	902	901	20 93 32 94 14 11	34 95 45 95 18 12	0 96 1 12	6 977 8 979 7 133	7 990 9 988 3 137	1001 997 142	1014 1006 126	1020 1012 150

<u>Sections</u> 406 x 178 x 54 kg/m 125 x 75 x 12 mm	54 kg/r 2 mm	m Grade Grade	ade 43A	Beam Angl	E)	ested	at 80%	of d	esign l	load -	BS449)			- 11	Date		26.6	.6.84
Concrete Floor 200 mm Slabs															Failur	e Time	70 п	min
						Temper	rature	, °C,	After	Various	s Time	s, min						
rnermocouple Location	6	9	6	12	15	18	21	24	27	30	35	40	45	50	55	09	65	70
Lower Flange F1	9	185	317	425	535	209	654	685	707	724	742	770	798	824	851	874	894	914
2 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7	85 91 104	178 204 180 205	341 341 313 333	415 440 419 431	533 538 531 534	606 606 603 602	655 652 651 649	687 683 683 680	709 705 704 702	728 722 723 719	747 738 740 738	776 765 767 766	806 794 796 795	835 822 822 822	862 852 850 851	885 877 874 874	903 896 892 893	922 914 910 911
Mean Lower Flange	91	190	323	426	534	604	652	684	705	723	741	692	798	825	853	877	968	914
Web & Position W1 (Exposed) W2 W3 W3 W4	107 96 103 133	192 184 195 217	295 299 304 319	377 389 384 394	469 490 482 483	537 556 550 547	585 605 600 594	620 639 635 628	648 663 662 655	669 685 685 677	700 715 716 708	727 736 737 734	745 765 767 757	775 796 800 789	803 826 830 819	833 853 857 847	856 873 878 869	878 894 898 889
Mean Exposed Web	110	197	304	386	481	547	296	630	657	629	710	733	758	790	819	847	698	890
Web # Position W5 (Unexposed) W6 W7	118 18 18	20 20 20 20	25 23 24 23	32 29 30 29	40 35 38 37	50 43 47 45	62 53 57 55	74 63 67 66	87 74 79 77	100 85 93 89	121 100 109 109	140 108 124 126	156 114 136 140	168 122 141 151	180 132 147 162	192 143 155	204 155 162 182	219 173 177 194
Mean Unexposed Web	18	20	24	30	37	46	57	67	79	92	110	124	136	145	155	165	176	191
Upper Flange F3 F5 F8	118 18 17	17 19 18 17	17 18 19	18 19 18	19 19 20 19	19 20 21 20	21 21 23 22	22 23 35 23	24 24 48 26	26 27 67 29	30 33 88 34	37 40 96 40	46 49 96 48	55 59 97 55	63 69 97 64	71 77 98 74	79 85 98 84	87 92 99 97
Mean Upper Flange	17	18	18	18	19	20	22	26	30	37	46	53	09	99	73	80	98	94
Exposed Flange (Angle) F10 F11	67 66 67	133 112 116	202 176 178	257 233 241	326 309 321	391 373 391	447 423 450	482 446 495	504 490 531	515 547 561	539 612 607	596 660 651	648 704 689	708 738 722	752 768 748	781 794 772	811 823 798	839 851 826
Mean Exposed Flange (Angle)	67	120	185	244	319	385	440	474	508	541	989	989	680	723	756	782	811	839
Unexposed Flange (Angle) W9 W10	25 26 24	41 43 40	69 69 99	99 103 100	138 142 143	181 185 189	225 229 234	268 271 276	308 308 313	343 342 346	393 391 394	434 432 433	469 467 468	501 500 500	531 530 531	560 560 561	588 588 588	613 614 613
Mean Unexposed Flange (Angle)	25	41	67	101	141	185	229	272	310	344	393	433	468	200	531	260	588	613
Angle Root 16	33 32 36	57 54 59	96 89 97	135 130 139	183 180 191	235 233 245	285 286 297	330 334 345	367 375 387	402 415 424	452 474 476	500 524 516	545 567 551	587 604 584	626 639 614	661 669 644	690 696 674	716 722 703
Mean Angle Root	33	56	94	134	185	238	289	336	376	414	467	513	554	592	626	658	687	714
Mean Atmosphere ISO Curve at 22°C Central Beam Deflection, mm	426 504 7	601 605 17	649 665 28	697 707 39	742 740 50	767 768 60	781 791 69	791 810 77	803 828 83	815 844 89	835 867 95	856 887 105	875 904 112	905 920 119	909 934 125	927 947 134	940 959 142	957 970 150

SHELF ANGLE FLOOR TEST B - TEMPERATURE DATA SHEET

TABLE 4

9.12.84

Date

(Tested at 60% of design load - BS449)

SHEET

TEMPERATURE DATA

U

SHELF ANGLE FLOOR

Beam Angles

43A 50B

Grade Grade

kg/m

x 54

TABLE 5 Sections

178 mm x 75 x 12 m SHELF ANGLE FLOOR TEST D - TEMPERATURE DATA SHEET TABLE 6

Grade 43A Beam Grade 50B Angles 406 x 178 x 54 kg/m 125 x 75 x 12 mm

mm Slabs

Concrete Floor

Sections

min Failure Time

11.7.84

Date

Beam size


406 x 178 mm x 54 kg/m

Angle size

125 x 75 x 12 mm

Bolts


M20 Grade 8.8



Dimensions in mm

SCHEMATIC ILLUSTRATION OF A TYPICAL TEST ARRANGEMENT

FIG. 1 (R1/8766)




TAPERED PRECAST CONCRETE FLOOR - UNITS USED IN THE TEST

FIG. 2(a) (R2/6064)


FIG. 2(b) (R2/919)

PRECAST CONCRETE SLAB DESIGNS USED IN TEST

All dimensions in mm




14




F9, W9, W4, W5

W11, F6, W2, W12, W1, W8

15






ASSEMBLY OF CONSTRUCTION


FIG. 4






ASSEMBLY OF CONSTRUCTION

FIG. 5




CONSTRUCTION PRIOR TO TESTING

FIG. 6




CENTRAL VERTICAL DEFLECTION MEASURED ON THE 406×178 mm $\times 54$ kg/m BEAM DURING TEST A



COMPARISON OF FURNACE ATMOSPHERE TEMPERATURES

MEASURED IN TEST A WITH


INTERNATIONAL TIME/TEMPERATURE CURVE




LF, UF = Lower, upper flange
W = Web, EAF = Exposed angle flange

AVERAGE TEMPERATURES RECORDED AT DIFFERENT POSITIONS ACROSS A 406 x 178 mm x 54 kg/m SHELF ANGLE BEAM WITH 200 mm CONCRETE SLABS IN TEST A

FIG. 9 (R2/6065)




CENTRAL VERTICAL DEFLECTION MEASURED ON THE 406×178 mm $\times 54$ kg/m BEAM DURING TEST B



COMPARISON OF FURNACE ATMOSPHERE TEMPERATURES
MEASURED IN TEST B WITH
INTERNATIONAL TIME/TEMPERATURE CURVE


Temperature, °C




LF, UF = Lower, upper flange W = Web, EAF = Exposed angle flange

AVERAGE TEMPERATURES RECORDED AT DIFFERENT POSITIONS ACROSS A 406 x 178 mm x 54 kg/m SHELF ANGLE BEAM WITH 200 mm CONCRETE SLABS IN TEST B

FIG. 12 (R2/6066)





CENTRAL VERTICAL DEFLECTION MEASURED ON THE 406 x 178 mm x 54 kg/m BEAM DURING TEST C



COMPARISON OF FURNACE ATMOSPHERE TEMPERATURES MEASURED IN TEST C WITH INTERNATIONAL TIME/TEMPERATURE CURVE


FIG. 14






AVERAGE TEMPERATURES RECORDED AT DIFFERENT POSITIONS
ACROSS A 406 x 178 mm x 54 kg/m SHELF ANGLE BEAM
WITH 100 mm CONCRETE SLABS IN TEST C

FIG. 15 (R2/6067)




Cracks in 100 mm slab (a)




Uniform deflection of beam
OBSERVATIONS IN TEST C

FIG. 16




CENTRAL VERTICAL DEFLECTION MEASURED ON THE 406 x 178 mm x 54 kg/m BEAM AND CONCRETE SLABS DURING TEST D



COMPARISON OF FURNACE ATMOSPHERE TEMPERATURES

MEASURED ON TEST D WITH

INTERNATIONAL TIME/TEMPERATURE CURVE



AVERAGE TEMPERATURES RECORDED AT DIFFERENT POSITIONS ACROSS A 406 x 178 mm x 54 kg/m SHELF ANGLE BEAM WITH 100 mm CONCRETE SLABS IN TEST D

FIG. 19 (R2/6068)

APPENDIX 1 LOAD CALCULATIONS

406 x 178 mm x 54 kg/m UB Grade 43A 125 x 75 x 12 mm Shelf Angles Effective Span 4.5 m

Maximum safe	working	uniformly	distributed	load	= 271 k	N
Haville Sale	WOIKING	unitionini	arstrrbatea	Toau	- 2/ K	

... Operating at 80% of maximum = 217 kN 60% of maximum = 163 kN

Total dead weight of cover slabs and spreader beams = 72 kN

... Reaction on each shelf angle = $\frac{72}{2} \times \frac{1}{2} = 18 \text{ kN}$

Total force required on each shelf angle to produce maximum operating stress (165 N/mm²) in test beam = $\frac{271}{2}$ = 135.5 - 18 = 117.5 kN

Force required by each set of rams = $\frac{117.5 \times 1.6}{1.1}$ = 171 kN

... Force required by each ram = $\frac{171}{4}$ = 42.75 kN

Total hydraulic forces applied = $42.75 \times 8 = 342 \text{ kN} - \text{Test D}$

Total hydraulic forces applied for 80% loading = 236 kN - Test B 60% loading = 185 kN - Test C

406 x 178 mm x 54 kg/m UB Grade 50B 125 x 75 x 12 mm Shelf Angles Effective Span 4.5 m

Safe working uniformly distributed load = 378 kN

Tested at 40% of maximum UDL = 163 kN

Total dead weight of cover slabs and spreader beams = 72 kN

... Reaction on each shelf angle = $\frac{72}{2} \times \frac{1}{2} = 18 \text{ kN}$

Total force required on each shelf angle to produce $=\frac{163}{2}=81.5-18=63.5$ kN design stress in test beam

Force required by each set of rams = $\frac{63.5 \times 1.6}{1.1}$ = 92.36 kN

... Force required by each ram = $\frac{92.36}{4}$ = 23.1 kN

Total hydraulic force applied = $23.1 \times 8 = 185 \text{ kN}$

TEST A



WARRINGTON RESEARCH CENTRE

Fire Research, Testing and Consultancy

Warrington Research Consultants (Services) Limited Holmesfield Road Warrington WA1 2DS Tel: Warrington (0925) 55116 Telex: 628743 WARRES G W.R.C.S.I. 34140 25 May 1984 - LH/RC

Mr. G. Thompson British Steel Corporation Sheffield Laboratories Swindon House Moorgate ROTHERHAM

Dear Sir.

FIRE RESISTANCE TEST RESULTS

We confirm the results of a fire resistance test carried out on your behalf in accordance with BS 476: Part 8: 1972, on a steel beam of serial size 406 mm by 178 mm by 54 kg/m. Grade 50B, which supported precast reinforced concrete slabs of overall size 1550 mm long by 550 mm wide by 200 mm deep on each side of the beam. The concrete slabs were supported on a continuous angle of size 125 mm by 75 mm by 12 mm thick Grade 50B on each side of the web of the beam. A total load of 184.8 kN was applied to the concrete slabs at $^1/8$, $^5/8$ and $^7/8$ span positions. The load was calculated by the sponor to be 40% of the maximum allowable for the beam. The loading was applied at a distance of 500 mm away from the centre line of the beam and each side of the beam. The ends of the concrete slabs being supported by the steel beam, were bedded in a sand and cement mortar mix. The steel beam was unprotected. The test results were as follows:

Stability

: 94 minutes

Re-load Test

: Satisfied

Date of Test

: 24 May 1984

Our full report will follow in due course.

Yours faithfully,

L.HEALEY

Technical Officer -

Structural Fire Protection WARRINGTON RESEARCH CENTRE

WP Ref. 155

E.S. LONDON, A.M.C.T., C. Chem., F.R.S. C. B. SAYERS, B.Sc., A.M.C.T., C. Eng., M.L.E.E. F.D. WILLIAMS, F.C.A., F.C.C.A.

TEST B



WARRINGTON RESEARCH CENTRE

Fire Research, Testing and Consultancy

Warrington Research Consultants (Services) Limited Holmesfield Road Warnington WA1 2DS Tel Warnington (0925) 55116 Telex 628743 WARRES G

Mr. G. Thompson, British Steel Corporation, Sheffield Laboratories, Swindon House, Moorgate, Rotherham. W.R.C.S.I. No. 34478 27th June 1984 - LH/RC

Dear Sir,

FIRE RESISTANCE TEST RESULTS

We confirm the results of a fire resistance test carried out on your behalf in accordance with B.S. 476: Part 8: 1972, on a steel beam of serial size 406 mm x 178 mm x 54 kg/m, Grade 43A which supported precast reinforced concrete slabs of overall size 1550 mm long by 550 mm wide by 200 mm deep on each side of the beam. The concrete slabs were supported on a continuous angle of size 125 mm by 75 mm by 12 mm thick Grade 50B on each side of the web of the beam. A total load of 263 kN was applied to the concrete slabs at 1/8, 3/8, 5/8 and 7/8 span positions. The load was calculated by the sponsor to be 80% of the maximum allowable for the beam. The loading was applied at a distance of 500 mm away from the centre line of the beam on each side of the beam. The ends of the concrete slabs being supported by the steel beam, were bedded in a sand and cement mortar mix. The steel beam was unprotected. The test results were as follows:

Stability: 70 minutes Re-load test: Satisfied

Date of test: 26th June 1984

Our full report will follow in due course.

Yours faithfully,

(L. HEALEY)

Warrington Research Centre

E.S. LONDON, A.M.C.T., C. Chem., F.R.S.C. B. SAYERS, B.Sc., A.M.C.T., C. Eng., M.I.E.E. F.D. WILLIAMS, F.C.A., F.C.C.A.

TEST C



WARRINGTON RESEARCH CENTRE

Fire Research, Testing and Consultancy

Warrington Research Consultants (Services) Limited Holmesfield Road Warrington WA1 2DS Tel: Warrington (0925) 55116 Telex: 626743 WARRES G

W.R.C.S.I. 35217 - IH/IMC 7 January 1985

British Steel Corporation Sheffield Laboratories Swindon House Moorgate ROTHERHAM.

Dear Sirs,

FIRE RESISTANCE TEST RESULTS

We confirm the results of a fire resistance test carried out on your behalf in accordance with B.S. 476: Part 8: 1972 and to the draft amendment of the Standard, on a steel beam of serial size 406 mm x 178 mm x 54 kg/m, Grade 43A which supported precast reinforced concrete slabs of overall size 1550 mm long x 550 mm wide x 150 mm deep with one end of the concrete slabs tapering to 100 mm deep over a distance of 300 mm. The concrete slabs were positioned on each side of the beam. The concrete slabs were supported on a continuous angle of size 125 mm x 75 mm x 12 mm thick Grade 50 on each side of the web of the beam. The tapered ends of the concrete slabs rested on to the continuous angles. A total load of 184.8 kN was applied to the concrete slabs at 1/8, 3/8, 5/8 and 7/8 span positions. The load was calculated by the sponsor to be 60% of the maximum allowable for the beam. The loading was applied at a distance of 500 mm away from the centre line of the beam on each side of the beam. The ends of the concrete slabs being supported by the steel beam, were bedded in a sand and cement mortar mix. The steel beam was unprotected. The test results were as follows.

Stability (L/30): 43 minutes

Stability (L/20): 74 minutes (Test discontinued)

Re-load test : Satisfied

Date of Test : 19 December 1984

Yours faithfully,

L. HEALEY

Warrington Research Centre

E.S. LONDON, A.M.C.T., C. Chem., F.R.S.C. B. SAYERS, B.Sc., A.M.C.T., C. Eng., M.I.E.E. F.D. WILLIAMS, F.C.A., F.C.C.A.

TEST D



WARRINGTON RESEARCH CENTRE

Fire Research, Testing and Consultancy

Warnington Research Consultants (Services) Limite Holmesfield Road Warnington WA1 2DS Tel Warnington (0925) 55116 Telex 628743 WARRES G

W.R.C.S.I. No. 34142 - LH/SB

12th July 1984

British Steel Corporation Sheffield Laboratories Swindon House Moorgate, Rotherham

Dear Sirs,

FIRE RESISTANCE TEST RESULTS

We confirm the results of a fire resistance test carried out on your behalf in accordance with B.S. 476: Part 8: 1972, on a steel beam of serial size 406 mm x 178 mm x 54 kg/m, Grade 43A which supported precast reinforced concrete slabs of overall size 1550 mm long by 550 mm wide by 150 mm deep with one end of the concrete slabs tapering to 100 mm deep over a distance of 300 mm. The concrete slabs were positioned on each side of the beam. The concrete slabs were supported on a continuous angle of size 125 mm by 75 mm by 12 mm thick Grade 50 on each side of the web of the beam. The tapered ends of the concrete slabs rested on to the continuous angles. A total load of 352 kN was applied to the concrete slabs at 1/8, 3/8, 5/8 and 7/8 span positions. The load was calculated by the sponsor to be 100% of the maximum allowable for the beam. The loading was applied at a distance of 500 mm away from the centre line of the beam on each side of the beam. The ends of the concrete slabs being supported by the steel beam, were bedded in a sand and cement mortar mix. The steel beam was unprotected. The test results were as follows:

Stability: 29 minutes Re-load test: Satisfied

Date of test: 11th July 1984.

Yours faithfully,

(L. HEALEY)

Warrington Research Centre

E.S. LONDON, A.M.C.T., C. Chem., F.R.S.C. B. SAYERS, B.Sc., A.M.C.T., C. Eng., M.I.E.E. F.D. WILLIAMS, F.C.A., F.C.C.A.

INITIAL CIRCULATION

Swinden Laboratories

Teesside Laboratories

Mr. T.R. Kay Dr. B.R. Kirby Mr. J. Lessells Mr. D.E. Wainman Mr. E.F. Walker

Dr. R. Baker

GENERAL STEELS GROUP

BSC Plates, Sections and Commercial Steels

Steel House (Redcar)

Scunthorpe

Mr. G. Hogan Mr. R.A.C. Latter Mr. J.T. Robinson Mr. M.J. Thorndike Dr. M.J. Pettifor Dr. T.J. Pike

Lackenby

Mr. C. Mortlock Mr. E.D. Smith